Project No.	Doc. No.	Short Description	Issue Date	Revision
IGRPL_PS_JIN_01	IGRPL_PS_JIN_01-CS-01-00	RFP- Civil Construction	24-02-2025	0

REQUEST FOR PROPOSAL

FOR

CONSTRUCTION OF CIVIL FOUNDATIONS

AND

OTHER CIVIL WORKS FOR 15 TPD BIO-CBG PROJECT

0	24-02-2025	Issued for	TK	AS	MS	AK
Rev.No.	Issue Date	Description	Prep.By	Rev. By	App.By	Proj.Mgr

Client	IOC GPS Renewables Pvt. Ltd.	**IGRPL (JV Between IOCL & GPS Renewables**
EPC Company		**GPS Renewables Private Limited**

Introduction:

GPS Renewables is a Bangalore based cleantech firm founded in 2012 currently focused on bio-methanation technologies to solve the organic waste management challenge, accelerate the substitution of fossil fuel with bio-energy, and play a key role in mitigating climate change. Our proprietary, advanced technology has been implemented on various scales across India, Bangladesh, and Sri Lanka.

We are looking for civil contractor(s) for the construction activity of the Bio-CBG Plants at our **Jind Location.** Proposals are invited from the contractor(s) of repute having adequate experience and well-established in the civil construction line for execution of similar works of comparable magnitude.

The details of the project and requirements are provided below.

1.	**Nature of work**	CONSTRUCTION OF DIGESTER TANKS AND CIVIL WORKS FOR EQUIPMENT, PEB, LT BUILDING, INTERNAL ROADS, DRAINS ETC. AND OTHER CIVIL WORK FOR BIO-CBG PROJECT.
2.	**Location**	Jind
3.	**Time of Completion**	210 DAYS

1. The decision of acceptance of the offers rests with the Owner and reserves itself with full rights for the following without assigning any reason whatsoever
   b. Not accept the lowest tender
   c. To reject any or all the tenders

INSTRUCTIONS TO BIDDER	
1	The Schedule of Rate shall be read with all the other sections of this bidding document including technical specification, preamble, general and special conditions of contract, safety requirements, EHS norms, etc.
2	QRO (quoted rate only) to be quoted & the rates quoted by the contractor should be inclusive of all material, labor, power equipment, concrete pump tools/tackles, centering, shoring, lifts, leads, scaffolding, excise & all taxes & duties.
3	The bidder is deemed to have studied the drawings, specifications and the details of work to be done within the schedule and should have acquainted himself with the conditions prevailing at the site.
4	The OWNER reserves the right to interpolate or extrapolate the rates for any new items of work not covered in the schedule of price from the similar items already available in the schedule of rates. All the works shall be measured upon completion and paid for at the rate quoted and accepted in the "Schedule of Price". In case any activity though specifically not covered in the schedule of rates descriptions but the same is covered under the scope of work/scope of supply/specification drawings etc. no extra claim on this account shall be entertained since the schedule of price is to be read in conjunction with all other documents forming part of the contract.
5	The Bidder is to quote for all items and all the quantities.**: IOCL JIND BOQ** Phase-1 The total construction work is divided into two phases: Phase-1 (Substructure) and Phase-2 (Superstructure). The contractor is required to complete both phases at the same quoted and finalized unit rate until the civil structure is fully completed in all aspects.
6	If the Bidder does not quote for any of the items, the highest rate quoted by any other bidder will be applicable for evaluation, but the lowest rate quoted by any other bidder shall be considered for payment in case the job is awarded to the bidder.
7	All items of work mentioned in the Schedule of Rates shall be carried out as per the specifications, drawings, and instructions of OWNER/Engineer-in-Charge, and the rates are deemed to be inclusive

	of material, consumables, labor, supervision, testing, tools, and tackles and detailing of construction/fabrication drawings, wherever required as called for in the detail specification and conditions of the Contract.
8	OWNER reserves the right to cancel/delete/curtail any item or group of work if necessary. Such a step shall not be construed as a reason for changing the rates.
9	Amount to be quoted in the nearest Indian Rupees only
10	The drawings included in the bidding document are for reference and a general understanding of the scope of work. Any variation in dimension, levels, and details in the working drawing shall not be reason by any means for change in quoted rates.
11	The contractor may visit the site before quoting.
12	The quantities shown against the items are only approximate, and tentative & may vary to any extent individually (increase or decrease). No claim shall be entertained during the currency of this contract towards any items due to the above.
13	Material shall be of good, approved, acceptable quality & purchased from an approved source; got approved by the engineer in charge before usage and meeting all relevant codal norms.
14	Work shall be carried out as per latest construction drawings, and specifications & carried out to the satisfaction of the engineer-in-charge.
15	Fabrication drawings for structural steel work shall be prepared by the contractor and Two copies of such drawings shall simultaneously be submitted to clients and the Consultant office for Information only. It is the contractor's responsibility to correctness/ soundness of the drawings & see to it that all the structural requirements as per the construction (GFC) drawings issued by us are met.
16	Bar bending schedule drawings, shop drawings, method statements, rate analysis (if any) for extra items, and as-built drawings shall be prepared by the contractor.
17	The contractor's scope of work shall include the complete civil work of the subject plant as per the estimated bill of quantity inc. Cement, TMT bar, any Structural steel, Sand, Aggregates & any other raw material used in the construction works. All other materials (if any) other than those above will be in the scope of the Contractor including scaffolding/temporary structure for construction, shuttering material, etc.
18	**Quality Assurance/ Quality Control Requirements** 1. The contractor shall ensure compliance with the approved Inspection and Test Plan (ITP) issued by GPS Renewables. Refer to Annexure-1 to be followed by the contractor. 2. All Requests for Inspection (RFIs) must be raised and submitted promptly for inspection activities as per the ITP. 3. The contractor shall prepare and provide all relevant QA/QC documentation in real-time for review and endorsement, ensuring traceability and compliance with project requirements. 4. Field Laboratory: The contractor shall set up a field laboratory at the site to conduct routine tests on construction samples as per project requirements.
19	**HSE guidelines** are to be assured by the contractor as issued by the GPS renewables. Refer to Annexure 2.
20	Contractors must ensure the Water/Slurry retaining structures' leakproof construction—digester and all other tanks. No extra cost/claim will be entertained for Nozzel Fixing grouting with chemicals.
21	It is the contractor's responsibility to build the water-retaining structure as per the design and specifications. Therefore, the contractor is responsible for arranging pumps, pipelines, and necessary tools tackles, and manpower to perform the hydro test on the tank. Water will be provided by GPS at a single point.
21	02 Nos. of Boom Placers are required for the Digester and RCC Tanks Casting.
22	The contractor shall conduct as many tests on materials, intermediate products such as the Slump cone test/ compressive test, and sieve Analysis at his own cost. Mix Design of different grades of concrete M15, M20, M25, and M30 along with the trail mix is in the scope of the Civil Contractor. He shall also if required by the Project In-charge, arrange for such tests & maintain Site Test Report books at each works site. If the quality of materials appears to be inferior or the portion of the work is found to be defective or unsound, the contractor may be asked to remove & or pull down and re-execute the same at his own cost. The contractor shall bear all costs in this regard, without any relaxation regarding the period of the contract.

23	The complete civil works are to be executed as per the IFC drawings issued at the site level for every structure.
24	All civil works shall be executed in strict compliance with the relevant IS standards and CPWD specifications.
25	Scope Matrix is to be considered in conjunction with the RFP. Refer to Annexure-3

SECTION-I- GENERAL INSTRUCTION/ QUALITY/ MATERIAL/ HSE

1.1 The contractor should always remain available at the work site, but where it is not so possible for him to do so, he must appoint a representative/technical supervisor for the purpose who would be duly authorized by the contractor to receive instructions.

1.2 The contractor shall provide sufficient plant, equipment, and labor and shall work such hours and shifts as may be necessary to maintain the progress schedule. The working and shift hours shall comply with all Govt. rules and regulations in force from time to time during the entire period of execution of the civil work.

1.3 The contractor should get the sample of all the materials approved by the Project In-charge, before collecting the same for use at the work site. The sample is sealed & shall' be kept in the custody of the Project In charge.

1.4 The contractor shall have to test the strength of cement concrete reinforced for each day's casting as per Building Construction Department codes/relevant codes. Achievement of the prescribed cube strength is a must. The cost of concrete cube Moulds, curing, carriage of cubes to and from the testing laboratory, and all other incidental charges incurred in this regard shall be borne by the contractor.

1.5 The contractor shall conduct as many tests on materials, intermediate products such as the Slump cone test/ compressive test, and sieve Analysis at his own cost. Mix Design of different grades of concrete M15, M20, M25, and M30 along with the trail mix is in the scope of the Civil Contractor. He shall also if required by the Project In-charge, arrange for such tests & maintain Site Test Report books at each works site. If the quality of materials appears to be inferior or the portion of the work is found to be defective or unsound, the contractor may be asked to remove & or pull down and re-execute the same at his own cost. The contractor shall bear all costs in this regard, without any relaxation regarding the period of the contract.

1.6 The contractor shall conduct as many tests on materials, intermediate products such as the Slump cone test/ compressive test, and sieve Analysis (if required) at his own cost. He shall also if required by the Project In-charge, arrange for such tests and maintain Site Test Report books at each works site. If the quality of materials appears to be inferior or the portion of the work is found to be defective or unsound, the contractor may be asked to remove and or pull down and re-execute the same at his own cost. The contractor shall bear all costs in this regard, without any relaxation regarding the period of the contract.

1.7 Quality Assurance/ Quality Control to be assured by the contractor as per the QAP issued by the GPS renewables.

1.8 The contractor's scope of work shall include the complete civil work of the subject plant as per the estimated bill of quantity including Cement, TMT bar, any Structural steel, Sand, Aggregates & any other raw material used in the construction works. All other materials (if any) other than those above will be in the scope of the Contractor including scaffolding/temporary structure for construction, shuttering material, etc.

1.9 Free electricity and water shall be supplied by the owner at one point & routine maintenance is in the scope of the Civil Contractor.

1.10 Construction Power: A single point of electricity will be provided by GPS. It will be the responsibility of contractor to draw power from that single point of source. Required Cables, Panel / Distribution board etc. to working area will be in the scope of contractor including maintenance.

1.11 Construction Water: GPS will provide a single point of water supply for construction work only not for RMC plant. It will be the responsibility of contractor to install pumps, pipes and other infrastructure to

draw the water from a single source to working area of water supply provided by GPS, contractor to ensure the maintenance on routine Baise.

1.12 The detailed contract incorporating the scope of work and other relevant terms would be executed with the work order issued.

1.13 Health, Safety & Environment are to be assured by the contractor during the entire execution of the works & following the Safety policy as issued by GPS Renewables. Refer to Annexure-2 for HSE requirements to be followed by the contractor.

SECTION-II- CIVIL WORK COST/BOQ/VARIATIONS IN QUANTITIES

2.1 The rates in bills of quantities are to be filled and signed on each page.

2.2 The Contractor is expected to quote the rate for each item after careful analysis of the cost involved for the performance of the complete item considering all Specifications and Conditions of the Contract. This will avoid additional loss of profit or gain in case of curtailment or change of specifications for any item.

2.3 In case, it is noticed that the rates quoted by the contractor for any items are unusually high or unusually low it will be sufficient cause for the rejection of the tender unless the Owner is convinced about the reasonableness of the rates on scrutiny of the analysis for the such rate to be furnished by the contractor on demand. Notwithstanding anything wherein stated, the rates once accepted by the Contractor shall be final and shall not be subject to any claim either on account of the un-workability of rates or on any other ground whatsoever.

2.4 QRO (quoted rate only) to be quoted & the rates quoted by the contractor should be inclusive of all material, labor, power equipment, concrete pump tools/tackles, centering, shoring, lifts, leads, scaffolding, excise & all taxes & duties.

2.5 The detailed contract incorporating the scope of work and other relevant terms would be executed with the work order issued.

2.6 The rate quoted shall be valid for 3 months.

2.7 The quantities/areas shown against the various items in the BOQ are only approximate and may vary to any extent individually. Any increase or decrease in the quantities shall not form the basis for alteration of rates quoted.

2.8 In case any new/extra items are specifically not covered in the schedule of rates descriptions but the same is covered under the specification of issued drawings. Extra claims on this account shall be entertained along with the submission of proper rate analysis.

2.9 Any civil work amendment or change at the site shall require prior approval from the Site In-Charge, before the commencement of work. No work shall be allowed without such approval. Any work executed without proper authorization will be considered null and void.

2.10 All civil works shall be executed in strict compliance with the relevant IS standards, Mode of measurement, and CPWD specifications wherever applicable.

2.11 The contractor shall use the building material of standard make specified in the Schedule of Approved Makes OR the Contractor has to take prior approval of any other material which has to be used from the Project In-charge.

SECTION-III- APPROVED MAKES/ LIST OF STRUCTURES

Table 1- TENTATIVE LIST OF STRUCTURES

Sl.No.	Tentative list of Structures	Nos.	Tentative Size & Area	Remark
1	RCC Digestor tanks	3	32diamtr X 8.25mtr	Construction to be done from slip form technique
2	RCC LDT tank	1	11 dia mtr X 5 mtr	
3	LT Control Room Building	1	42mtr X 12mtr	
4	Leachate Tank	1	3m X 2m X 2m	
5	PEB Shed Civil Work- Manure, HP Compressor, HWG, BU, Decenter, Workshop	1	4500sqm	
6	Internal Road	1	800mtr X 6mtr wide	SFRC-M20 (150mm th)
7	Internal Drain	1	1200 rmt	RCC/Brickwork
8	Weigh Bridge foundations	1	15m X 4m	
9	Metering Room	1	150Sqm	
10	Paddy Storage Yard	1	800 Sqm	
11	Compost Pad	1	7000 Sqm	SFRC-M20 (100mm th)
12	Parking Area	1	500 sqm	Paver block-M30
13	Equipment Foundations			
14				

Table 2- LIST OF APPROVED MAKES

Sl.No.	MATERIAL	APPROVED MAKE/ APPROVED AGENCY
1	Anti-termite emulsifiable concentrate	As per CPWD/PWD specifications and ISI marked
2	Damp-proof materials/ waterproofing compound	Pidilite. Fosroc, Sika, Shalimar
3	Reinforcement steel	Tata, SAIL, RINL as approved (Primary manufacture)
4	Structural steel section	Tata, SAIL, RINL as approved (Primary manufacture)
5	White cement	JK white, Birla white
6	Ordinary Portland Cement	Ultratech, Shree, ACC as per I.S. 455 as approved
7	Aluminum glazing section	Hindalco, Jindal
8	Locks, Door Fittings, closers, Handles, Mortise lock (door fittings)	Dorma/Godrej ISI marked
9	Distemper	Berger, Asian paints, Nerolac as approved

Sl.No.	MATERIAL	APPROVED MAKE/ APPROVED AGENCY
10	Synthetic enamel paint	J & N, Berger, Shalimar, Asian paints, Nerolac, ISI as approved
11	Plastic emulsion paint	Asian paints, Berger, Nerolac, ICI, J&N, Shalimar
12	Waterproof cement paint	Snowcem, Asian paints, Nerolac, Berger as approved
13	Glazed ceramic tiles	Johnson, Somany, Kajaria, Bell
14	Unglazed ceramic tiles	Johnson, Somany, Kajaria, Bell
15	Vitrified tiles	Johnson, Somany, Kajaria, Bell
16	Flush doors	Anchor, Kitply, Greenply, Moyur, Woodcraft, Alpro, I.S.I. Marked

SECTION-IV- LIST OF EQUIPMENT, TECHNICAL/SKILLED/UNSKILLED MANPOWER

2.1 All kinds of lifting and handling equipment like hydra, cranes, hoists, etc. will be arranged by the Contractor as per the requirement of the site and project schedule.

2.2 The contractor needs to have ownership of the following Machinery or any other equipment/machinery in working condition and availability of the same as required at the Project site.

2.3 A list of plant/equipment to be deployed for the work is to be submitted.

2.4 Whereas it is the entire responsibility of the Contractor to deploy sufficient construction plant and equipment to ensure compliance with his obligations under the Contract. This list constitutes the Employer's estimate of the minimum essential basic holding of construction plant and equipment, which the Contractor must own or have long-term leasing arrangements (Applicant to indicate if the equipment is proposed to be Owned / Leased / Purchased)

Table 3- LIST OF PLANT & MACHINERY

Sl. No.	Plant and Machinery	Mfg. Yr. & Number
1	**Machinery's**	
1.1	Hydraulic Excavator /JCB Backhoe Loader	
1.2	Dumper/Tipper	
1.3	Generator Set	
1.4	Water tanker	
1.5	Concrete/Transit Mixer	
1.6	Needle Vibrator	
1.7	Welding Machines/ Related Items for Structural Works	
1.8	Concrete Boom Placer	

Sl. No.	Plant and Machinery	Mfg. Yr. & Number
1.9	Concrete Batch Mixing Plant	
1.10	Hydra with hoists	
1.11	Tower Crane/ Truck-mounted Crane	
1.12	Steel Shuttering	
1.13	Slipform Shuttering Material for Concrete Tanks	
2	**Laboratory**	
2.1	Cube Testing Equipment (CTM, Moulds, Sieve analysis, etc.)	
2.2	Auto Level	
2.3	Total Station	
3	**Any other Items**	

2.5 The Contractor shall cover his workers and staff under the ESI & PF scheme and comply with local laws and statutory requirements.

2.6 The Contractor shall take a minimum amount of third-party insurance and workmen compensation insurance.

2.7 A list of personnel to be deployed for the work is to be submitted.

2.8 The CV of the proposed Technical staff especially for the Project Manager, Civil Site Engineer, and QC Inspector shall be submitted for review and approval by the GPSR before deployment.

2.9 If the contractor fails to deploy a qualified QC Inspector as required, the next payment will be withheld until full compliance is achieved to GPSR's satisfaction.

Table 4- LIST OF MANPOWER/TECHNICAL STAFF

Sl. No.	Manpower	Number
1	**Technical Manpower**	
1.1	Project Manager- (Civil/Mech.)	
1.2	Civil Site Engineers (Jr./Sr.)	
1.3	Qualified QC Inspector	
1.4	Surveyor	
1.5	Supervisor/Foreman-Civil/Mech.	
1.6	Skilled Labor (Carpenter/ Bar Bender/Mason/Welder)	
1.7	Un-skilled Labor	
1.8	Electrician	
1.9	Safety Supervisors	